# Quality Assurance Tests for RE4 Nicolas ZAGANIDIS & Anton DIMITROV

on behalf of the RPC-TC Team

A full central control on the production at the level of components & chambers:

1.) Definition of a common QA frame among the assembly sites, subcontractors, suppliers
2.) QA definition for each step of the production

3.) Documentation

### Guarantee Reliability + Traceability

Based on the valuable experience (Barrel &

- Endcap) we define several steps of QC :
  - **QC-1: Components**
  - QC-2: Gaps
  - QC-3 : Chambers (Assembly sites)
  - QC-4 : Chambers & Super Modules (904)
  - QC-5 : Commissioning at P5

For each step :

QA protocols to assure manufacture process reliability QC protocols to select the "good" objects which are inside the technical specifications ranges Documentation protocols : RPC Construction DB





### Responsibilities

- QC-1 : RPC-Technical Coordination
- QC-2 : Kodel + Assembly sites
- QC-3 : Assembly sites (CERN, Mumbai, Ghent)
- QC-4 : RPC-Technical Coordination (904 team)
- QC-5 : RPC- Technical Coordination (Commissioning team @P5)

#### QC-1 :

## Bakelite (HPL panels) Front End Boards Distribution Boards Adaptor boards

### QC-1 : Bakelite

- Panels 1.6m x 3.2m: (660)
- Production site : resistivity, thickness, roughness ightarrow
- Pavia : Resistivity, Color code, Labeling & DB  $\rightarrow$
- RIVA : HPL Cutting into 3 pieces: V.I. size & corners  $\rightarrow$
- GT : Polishing surface : Visual Inspection surface quality → Shipment to CERN
- CERN : Visual Inspection and Final Acceptance if OK  $\rightarrow$  Shipment to KODEL

#### **END of CERN BAKELITE ORDER**

### QC-1 : Bakelite

- Production Batch all the data valid for a complete batch of up to 50 bakelites (craft paper, weights, number of papers, press thermal cycle details etc.)
- Puricelli Data primary data from Puricelli are to be uploaded in the database (temperature, humidity, resistivity, st.dev.resistivity, resolution)
- Pavia Data measurements in Pavia uploaded in database (on top of the main measurements color code and accept/reject fields are added)
- Multiple Bakelite Measurements structure for multiple measurements (multiple measurements are foreseen for the small/cut pieces)

C:\Users\A	Anton Dimitrov\	Desktop\Report	t.htm	(5 + Q)	K 🗖 BAKELIT	-	🦲 Anton Dim	itrov - Outloc	k Web {	🗿 PURICELLI DATA	A X				) <mark>→</mark> ×
x bing					📣 f					<mark>ዾ</mark> 🔅					000
Bakelite Code	Production Number	Production Batch	Slot	Position	Thickness	Measure Date	Temperature Measure	Humidity	Rho20	Sigma Rho20	Resolution	Comments	User	Modified on	
2A07a110411010153	153	7	Α	2	2	011-04-15 00:00:00	18.8	38.45	1.17	0.12	0.10		UZUNOVA	2011-05-11 12:19:2	!0
2A07a110411010153	153	7	Α	2	2	011-05-22 00:00:00	18.8	38.45	1.17	0.12	0.10		UZUNOVA	2011-05-11 17:20:4	8
3A07a110411010154	154	7	Α	3	2	011-04-15 00:00:00	18.8	38.37	1.21	0.17	0.14		UZUNOVA	2011-05-11 12:19:2	.0
3A07a110411010154	154	7	Α	3	2	011-04-13 00:00:00	18.8	38.37	1.21	0.17	0.14		UZUNOVA	2011-05-11 17:20:4	8
5A07a110411010156	156	7	Α	5	2	011-04-15 00:00:00	18.8	38.20	2.00	0.32	0.16		UZUNOVA	2011-05-11 12:19:2	.0
1B07a110411010157	157	7	В	1	2	011-04-15 00:00:00	18.8	38.95	1.97	0.36	0.19		UZUNOVA	2011-05-11 12:19:2	.0
2B07a110411010158	158	7	В	2	2	011-04-15 00:00:00	18.8	38.87	1.64	0.32	0.19		UZUNOVA	2011-05-11 12:19:2	.0
3B07a110411010159	159	7	В	3	2	011-04-15 00:00:00	18.8	38.78	1.34	0.21	0.16		UZUNOVA	2011-05-11 12:19:2	.0
4B07a110411010160	160	7	В	4	2	011-04-15 00:00:00	18.8	38.70	1.13	0.23	0.20		UZUNOVA	2011-05-11 12:19:2	10
5B07a110411010161	161	7	В	5	2	011-04-15 00:00:00	18.8	38.62	1.09	0.13	0.12		UZUNOVA	2011-05-11 12:19:2	.0
1C07a110411010162	162	7	С	1	2	011-04-15 00:00:00	18.8	39.37	4.57	1.08	0.24		UZUNOVA	2011-05-11 12:19:2	20
2C07a110411010163	163	7	С	2	2	011-04-15 00:00:00	18.8	39.28	3.66	0.82	0.22		UZUNOVA	2011-05-11 12:19:2	20
3C07a110411010164	164	7	С	3	2	011-04-15 00:00:00	18.8	39.20	2.93	0.58	0.20		UZUNOVA	2011-05-11 12:19:2	20
4C07a110411010165	165	7	С	4	2	011-04-15 00:00:00	18.8	39.12	2.40	0.70	0.29		UZUNOVA	2011-05-11 12:19:2	20
5C07a110411010166	166	7	С	5	2	011-04-15 00:00:00	18.8	39.03	2.05	0.44	0.22		UZUNOVA	2011-05-11 12:19:2	20
1D07a110411010167	167	7	D	1	2	011-04-15 00:00:00	18.8	39.78	8.72	2.91	0.33		UZUNOVA	2011-05-11 12:19:2	20
2D07a110411010168	168	7	D	2	2	011-04-15 00:00:00	18.8	39.70	7.48	2.08	0.28		UZUNOVA	2011-05-11 12:19:2	20
3D07a110411010169	169	7	D	3	2	011-04-15 00:00:00	18.8	39.62	6.59	1.74	0.26		UZUNOVA	2011-05-11 12:19:2	20
4007-110411010170	170					011 04 15 00.00.00	10.0	20.52	5.07	4.45	0.05		117010014	2011 05 11 12.10.2	
													EN 🔺	🕨 🛱 .al 🏟 16	18:39 5.5.2011

## QC-1 : FEB (Pakistan)

Dedicated format file is to be filled and uploaded in the DB before shipment; if  $OK \rightarrow$  shipment to CERN

- FEB\_ID (CMS barcode)
- Time\_Code
- Delay\_ns
- Date and Time of Test
- Test\_Bench (or Manufactored by)
- Specification File (the output of the labview program in jpeg or png format)
- 4 Values Hardware THR 1, THR 2, THR 3, THR 4
- 4 Values Vmon1, Vmon2, Vmon3, Vmon4
- Comments

#### QC-1 : Distribution Boards

Dedicated format file is to be filled and uploaded in the DB before shipment; if  $OK \rightarrow$  shipment to CERN

- Serial ID (CMS barcode)
- Date and Time of Test
- Site

#### QC-1 : Adaptor Boards

Dedicated format file is to be filled and uploaded in the DB before shipment; if  $OK \rightarrow$  shipment to CERN

- Serial ID (CMS Barcode)
- Date and Time of Test
- Site

## QC-2 : Gaps (Kodel)

Supplier : Kodel 660 Gaps / 12 months Very clear Gap specifications document : -Detailed QA procedures -Clear acceptance Protocol including the instrumentation to be used Upgrade Gap Structure and GUI in RPC construction database ready Verification of the data for each gap if OK then shipment to the 3 assembly sites one shipment /month, 12 shipments in total ~60 gaps/month

## QC-2 : Gaps (sites)

#### Final Acceptance tests : Assembly sites Ready :

- -QA procedure & QC tests
- -Tooling (handling of the gaps)
- -Instrumentation
- -Electronics
- Under Development : Software Tools (scripts)

Gap stands : CERN 10 slots ,U-Gent :5 slots,Mumbai :3 slots

## QC-2 : Gaps (sites)

Type of tests: Visual Inspection. Gas Tightness tests, Spacers Test Electrical & Dark currents Test Resistivity measurement (only in the sites) All HV values are corrected for P&T  $P_0 = 1010 \text{ mbar}, T_0 = 293 \text{ K}$ Construction Database : Gap passport Data verification algorithms applied for data import of all Gap Quality Certification Tests. QC rejection criteria implemented Storage area in a controlled Environment

Visual Inspection	Bending, thickness, HV connections, inlets outlets PET film condition, graphite uniformity (?) Report 2x (HPL Serial numbers + Resistivity color)	male connector , length of HV cable =0.75 m Report Data for all gaps Gaps stored in T (18-25) & humidity (25- 50%) controlled environment				
Leak test	<ul><li>@ 20 mbar,</li><li>@ 5 mbar only for Ref. value</li><li>for chamber leak</li></ul>	Threshold (@20mbar) Leak rate < 0.2mbar/10min @ 2 liters				
Spacers	@ 20mb	All spacers properly glued, 0 broken				
Dark current test I	I vs HV plot waiting time 20 min per point Gas mixture : standard, Flow =5 l/h, 48 hours P , T correction online	1,2,3,4,5,6,7,7.5,8,.8.5,9.0,9.1, 9.2,9.3,9.4,9.5,9.6,9.7, 9.8. 9.9, 10., 10.1 HV values @ 1010 mb & 293K Gap rejected if :I10кv > Imax Pressure, T and Humidity				
Dark current test II	I drawn @ HV=10.0 KV 24 hours period (normalized) registered Script to adjust HV vs (P, T) automatically	Gap rejected if at the end : I10KV > Imax Or I10KV Increase > 50% or OVC,Spikes of current present.				

Dark current III	Check the ohmic component → study correlation I6кV vs I9.5кV Waiting time 5 min	At the end of Dark current II test perform HV ramp-up: 1,2,3,4,5,6,7,7.5,8,.8.5,9.0, 9.1,9.2,9.3,9.4,9.5,9.6,9.7, 9.8. 9.9, 10., 10.1 Record P, T
	Barrel gaps with I6кv >1 uA rejected	➔ Ібк∨< О Register the data

Barrel : At the end of QC-2 : 8.5 % of gaps had been rejected

### Gap Visual Inspection

**HV Bakelite Barcode Label GND** Bakelite Barcode Label HV cable (new) GND cable (new) HV block (instead of Gap HV Pads) GND connection (new) HV Graphite Layer GND Graphite Layer **HV PET Coating GND PET Coating** Edges and Gas Corner Piece (instead of Gap Edges) Gas Inlets and Outlets (instead of Gas Inlets) Bending Reject\_Accept COMMENT

#### → ConstructionDB

#### **VISUAL INSPECTION PROTOCOL**

https://apex.cern.ch/	pls/htmldb_cmsr/f?p=1! 0 -	A R C X For	m on GAP VIS INS	2 X 🖉 Anton Dimitroy - Outlook Web	•					] x ∖☆ŵ
x bing			f	G Anton Dimitiov Couldok (rebin	P	* 19.				000
							Welcome: ANTON BA	ARREL ENDCAP U	OGRADE HELP	Logout HELP
UPGRADE BAKELITE	GAPS GAP TEST	S ADMIN								
VISUAL TEST RESISTIVITY TE	EST GAP HV TEST									
REGIDTER NEW GAP	VISUAL INSPECTION OF	GAP								
Kodel-CMS-RE4-2-B126     Kodel-CMS-RE4-2-B127								Са	ncel SAVE	3
	* GAP SERIAL NUMBER	Kodel-CMS-RE4-2	-B127 💌							
	Site	Select from list	•							
	Test Date									
	GND BAK. LABEL	GOOD	•	GROUND BAKELITE LABEL: 4B07a110411010	)160					
	HV BAK. LABEL	GOOD	•	HV BAKELITE LABEL: 4C08b110412010190						
	Gaps Edges	GOOD	•							
	Gap Inlets	GOOD	▼.							
	Graphite Layer	GOOD	•							
	Gap Hv Pads	GOOD	•							
	Bending	GOOD	•							
	Pet Film	GOOD	•							
	Reject Accept	ACCEPT	▼							
	Comments	ACCEPT REJECT			*					
					*					12.
								EN 🔺 🏴 🛱	(t)) .all 💸 27	16:28 7.6.2011

#### **Electrical tests**

• Gas :

95%Freon +5% Iso @Kodel 95.2%Freon + 4.5%Iso + 0.3%SF6 + 40%(Humidity)

• Maximum Value of the current (9.5KV @Kodel, 10KV @A.S.)

Gар Туре	RE4/3 "top narrow"	RE4/3 "top wide"	RE4/3 "bottom"	RE4/2 "top narrow"	RE4/2 "top wide"	RE4/2 "bottom"
I <sub>max</sub> (µA)	3.5	2.0	5.0	2.0	2.0	3.5

Maximum Value of the current @ 6KV: (1.5uA@Kodel, 0.5uA@A.S.)

#### GAP TESTS: HV TEST

		h (nlc (htm)	ldh.cmcr/f?n=11 0 =					0.11.1.11		-					<b>о х</b>
	ps://apex.cem.c	n/ pis/ num	lab_cmsi/i:p=1 🎾 +				× C Anton Dimit	rov - Outlook We	b	<b>1</b> 0					ม ม ม 
									2	****					000
											Welcome: A	NTON BARRE	L ENDCAP U	JPGRADE HEL	.P Logout
												HOME BARF	EL ENDCA	P UPGRADE	HELP
UPGRADE	BAKELITE	GA	PS GAP TEST	S ADMIN											
VISUAL TEST	RESISTIVITY	TEST (	GAP HV TEST												
HV TEST - GEN	IERAL INFOR	MATION													
														S	VE
* SI	ITE Select from	m list	•		СОММ	ENTS -									
* Date of Measu	ure											*			
* Cae miv	ura Salast fra	m liet													
		in list													
* Gas Flash St	ιαπ											4			
	Enter New	Tast Gana	aral information or Se	alact from existing	TESTS										
	LINEI NEW	Test delle		acci ii oin existing	12313										
HV EXISTING TE	STS														
8ELECT		EITE			C TYDE			COMMENTS	Number o	ECADE					
SELECT TEST	HV	904	10-JUN-11	Ereon 95.2% Iso	butan 3.5% SE	6.0.3%	22-JUN-2011 12:10	COMMENTS	Number o	I GAPS					
SELECT TEST	HV	CMS	04-JUN-11	Freon 95.2%, Iso	butan 3.5%, SF	6 0.3%	17-JUN-2011 17:23								
SELECT TEST	HV	CMS	02-JUN-11	Freon 95.2%, Iso	butan 3.5%. SF	6 0.3%	23-JUN-2011 16:46			-	with 10 (Test	]			
SELECT TEST	HV	904	02-JUN-11	Freon 95.2%, Iso	butan 3.5%, SF	6 0.3%	14-JUN-2011 12:19			- GAP	with riv Test:				
SELECT TEST	HV	ISR	02-JUN-11	Freon 95.2%, Iso	butan 3.5%, SF	6 0.3%	25-JUN-2011 11:58		2	• Ko	odel-CMS-RE4-2-B124	J			
javascript:; TEST	HV	Ghent	01-JUN-11	Freon 95.2%, Iso	butan 3.5%, SF	6 0.3%	18-JUN-2011 11:54								14
	0											EN	- P 🛱	🌵 all 😽	16:31 27.6.2011

### Leak Tests

- The gas tightness is controlled by measuring the stability of an applied overpressure of 20 mbar in a fixed time of 600 seconds using a pressure sensor (Sensor Technics CTE7000) and a 20 bit ADC Picolog recorder with 20 bit resolution.
- Acceptable pressure drop values are defined as function of the Gap Volumes:

With the Water Column Method, for a Volume of 2 liters the acceptable drop of the water level is 1 mm /600sec, is equiv. to 0.2mbar/600sec = 6.6 10\*-4 [mbar.l/sec] which is 0.7 times less than the BS EN13184:2001 Standard acceptable leak rate (=10\*-3[mbar . l/sec] ).

Leak measurement @ 5mbar taken as reference value for the chamber leak test

#### Spacer strength test

- The Gaps are subjected to an overpressure of 20 mbar to check the spacers tightness.
  - A mask made of 0.2mm thick PET film, where the shape of the spacers and the positions are properly drawn, is positioned on the gap.
  - A 20 hPa pressure is applied to the gap. Each spacer is pressed and the variation of the pressure is reordered.
  - The gas gap is qualified when no spacer causes a shift larger than 1 mbar.
  - All the data will be recorded in the DB

#### Gap Passport

GAP PASSPORT - Mozilla Firefox									
<u>Eichier Édition Affichage His</u>	itorique <u>M</u> arque-pages <u>Q</u> utils <u>?</u>								
© Indico [MUON - Mu × □r	pc-cms-re4-upsco 🗵 😻 Théorie   APC - Astr 🛛 🌇 Institut Astrophysiq 🗴 🌀 CRAL - Stages d	le M2 🙁 🚼 cra lyon theorie - R 🗵	GAP PASSPORT × + ·						
(←) Cern.ch https://ap		SN:22 ☆ - C 🚼 - cra lyon theorie	۰ 🔎 💁						
🔎 Les plus visités 🕋 Eloa 💶 RP	2 Comm < CMS < TWiki 🗍 EVO. The Collaboration 🐖 LHC OP el odbook 🦳 LHCstatus 🎔 CMS RE	PC Equipment @ cmsty 🗍 LHC - co	mmissionina »						
NOWE DANELITE	VAP TESTS CRAWDERS CRAWDER TESTS								
GAP PASSPORT GAPS OVERV	TEW REGISTER NEW GAP DEFINE GAP TYPE DEFINE GAS MIXORE DEFINE HW TOOLS								
	VISUAL INSPECTION - Latest Test								
TEST_GAP_10	TERT PARE OFF REJECT GRN HV HV GND HV GND HV GND	) HV PET GND Edges G							
GAP TYPE	IESI_DATE SITE ACCEPT BAK BAK Cable Cable block Conn. Graphite Grap LABEL LABEL Cable Cable block Conn. Layer Layer	prite Coating PEI & Gas in er Coating Conting Corner O	utlets BENDING COMMENTS						
B/SIZE 2	25-JUL-11 CMS ACCEPTED GOOD GOOD GOOD GOOD GOOD GOOD GOOD GO	DD GOOD GOOD GOOD G	000 6000 -						
Size 2: 2.339/ 1.169									
GROUND BAKELITE									
11	LEAK TEST - Latest Test								
HV BAKELITE 9	TEST DATE SITE REJECT Test Pressure Hardware Tool Overpressure Bad Spacers	Slope Slope /10min Leak Ra	ate COMMENTS						
MANIFACTURED BY KODEL	01-NOV-11 CMS ACCEPTED 20 Tool1 20 0	0000005734200133	266 -						
PRODUCTION DATE									
01/04/2011	(Bloquer)								
Shipment Date (Assembly) 07/07/2011	RESISTIVITY TEST TE	ST ID 26							
Reception Date (Assemly)	16.00 TEST	TYPE RESISTIVITY							
23/07/2011									
Assembly Site 904		DATE 13-OCT-11	55.0.0%						
GLOBAL RESULT	GAS ML	XURE Freen 94.7% + Isobutan 5% + S TART 11-00T-2011 17:16	F6 U.3%						
NOT TESTED	6.00 A	LPHA 1							
	4.00								
SELECT GAP	2.00 TEST RESULT: A	ACCEPTED							
• TEST GAP 1	1,000 1,400 1,800 2,200 2,600 3,000 3,400								
TEST GAP 10			<u> </u>						

### QC-3 : Chambers (sites)

#### QC-3-1: Chamber Assembly

#### QC-3-2 :

Performance Assessment of the detector with Cosmic Rays

## QC-3-1: Chamber Assembly (Sites)

- Very clear documentation how to build a chamber & QA procedures have been established and sent
  - Training sessions : 4 chambers built in February/March
- Exhaustive list of all the chamber's components established
- List of all the equipments & components for the infrastructure of the 3 sites
  - All components have been centrally purchased (cern)
  - Distribution among the 3 sites is on going
  - Clear QC procedures for the chamber validation

## QC-3-1: Chamber Assembly (Sites)

Clear QC procedures for the chamber validation before the performance assessment:

mechanics, gas tightness Cooling tightness Electrical tests / GAP (jupiter HV connectors) Electronics ON tests Strip Connectivity

#### • Construction Database :

Chamber passport

Data verification algorithms applied for data import of all Quality Certification Tests.

QC rejection criteria implemented

Electrical tests I (LVs)	LV analog = 7V LV digital = 7.5 Volts	Ianalog < 0.140 A / FEB connected Idigital < 0.260 A / FEB connected THR 1,2,3,4 =215 mV Vmon 1,2,3,4 =3500 mV
Electrical tests II (I <sup>2</sup> C)	LabView Only One module available Need to secure 4 modules Old components could be difficult to find (M. Tytgat)	Check for each Feb : Write & Read several values of Thresholds (Vthr, Vmon) 50, 215, 400
Connectivity tests	Pins 33-40 input pulse LVDS negative Output Pulse / strip duration > 200 ns Only one Frequency meter available (Produce 3+1 : Pigi)	Check if each strip is responding For Vmon =3500mV duration of output pulse ~100 ns
Leak test	@ 3 mbar	Cut under study to be defined (gas sector)
Cooling test	Argon @ 20bar	< $\Delta P = 100 \text{ mbar / half-hour}$ (to be verified)

#### QC-3-1 : Chambers Assembly (sites)

Dark current test /GAP (jupiter)	I vs HV plot waiting time 20 min per point Gas mixture : standard, Flow =5 I/h, 48 hours P , T correction online	0.1,1,2,3,4,5,6,7,7.5,8,.8.5, 99.1,9.2,9.3,9.4,9.5,9.6,9.7 , 9.8. 9.9, 10., 10.1 HV values @ 1010 mb & 293К rejected if I10кv > Imax Pressure, T and Humidity
Dark current test II / GAP (jupiter)	I drawn @ HV=9.7 KV 3 days period registered Script to adjust HV vs (P, T) automatically	Gap rejected if at the end : I9.5KV > Imax or I9.5KV Increase > 50% or Spikes of current present.

#### Chamber Components : QC-3-1



Bottom Gap: TEST_GAP_1	Top Wide Gap: TEST_GAP_12	Top Narrow Gap: TEST_GAP_3
New Bottom Gap: Select Bottom GAP	New Top Wide Gap: Select Top Wide GAP	💌 New Top Narrow Gap: Select Top Narrow GAP 🛛 💌

#### QC-3-2 : Performance Assessment(Sites)

Validation of the RPC performance with Cosmic Rays Chambers placed horizontally in Hodoscope with a controlled Temperature Humidity Environment (T=20,H=35%-55%)

Muon Trigger system generated by 2 layers of scintillators CMS Gas mixture : 95.2%Freon+4.5%Iso+0.3%SF6 +40%(Humidity) Gas T & Humidity monitored

DAQ : VME based, TDV Caen V1190A-128 ch in all 3 sites

*On-line* : CERN & BARC same software (cern) U-Ghent different (VME bridge) status : under Development

*Off-line* : the same software in the 3 sites (CERN team) status :under development

#### QC-3-2 : Performance Assessment(Sites)

## Check for noisy & absence of dead strips Performance Assessment per Gap and Global

Chamber performance	Cosmic rays Hodoscope	HV=8.7,8.8,8.9 ,9, 9.1,9.2,9.3,9.4, 9.5, 9.6,9.7, 9.8, 9.9, 10., 10.1 KV @ (1010mb, 293K), THR=215mV Plots:
under discussion		Efficiency, noise rate, noise profile, cluster size, strip multiplicity, number of clusters, strip profile, streamer, dark current

#### **Construction DB in progress** Certification Rate : One Stand / month

#### CHAMBER PASSPORT

Chamber_Construction - Windows Internet Explorer		
🔆 🔄 🗢 🥅 https://apex.cern.ch/pls/htmldb_cmsr/f?p=106:20:3129631994273703::	NO::P20_CH_ID,P12_CH_ID:462,462	🔒 🔄 🗙 🚼 Google
Favorites Chamber_Construction		
CHAMBER NAME: <u>W-2/RB2 in/1</u> , CHAMBER TYPE: <u>RB2-2in-Right</u> , CHAMBER LOC	ATION: RPC BARREL, WHEEL -2, SECTOR 1	Welcome: UZUNOVA BARREL ENDCAP UPGRADE HELP Logout
		HOME BARREL ENDCAP UPGRADE HELP
SELECT WHEEL/SECTOR/CHAMBER CHAMBER PASSPORT CHA	MBERS' ELEMENTS CHAMBERS' TESTS	
CHAMBER ID     CHAMBER NAME     CHAMBER TYPE     SERVICE EXIT       462     W-2/RB2 in/1     RB2-2in-Right		
ETA PARTITION: BACKWARD		
EFFICIENCY	MEAN CLUSTER SIZE IN	NOISE RATE BACKWARD
120.00 100.00 80.00 60.00 40.00 20.00 9,000 9,000 9,200 9,400 9,600 9,600 9,800	3.00 2.50 1.50 9,000 9,200 9,400 9,600 9,800	6 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0
TEST LOCATION: BARI DATE of TESTS: 28-AUG-06	TEST LOCATION: <u>BARI</u> DATE of TESTS: <u>28-AUG-06</u>	TEST LOCATION: BARI DATE of TESTS: 28-AUG-06
ETA PARTITION: FORWARD		
EFFICIENCY	MEAN CLUSTER SIZE IN	NOISE RATE FORWARD
100 90 70 90 90 9,000 9,200 9,400 9,600 9,800	3.00 2.80 2.40 2.40 2.20 1.80 1.60 1.40 1.20 9,000 9,200 9,400 9,600 9,800	50 80 75 70 65 60 55 9,000 9,200 9,400 9,600 9,800 9,800
DATE of TESTS: 24-AUG-06	DATE of TESTS: 24-AUG-06	DATE of TESTS: 24-AUG-06

## QC-4: RPCs (904)

#### QC-4-1:

Acceptance tests of the RPCs & Preparation for P5 QC-4-2:

> Assembly of the SuperModule & Final Acceptance Test (Long Term) Before transport to P5

## QC-4: RPCs (904)

✓ Dedicated area in the 904

- ✓ Dark currant, leak, connectivity tests of the chambers before SM
- ✓ Assembly of the Super Module :
  - mount TWO chambers with similar plateau on the Al Frame
- ✓ Gas Leak, cooling test of the SM
- $\checkmark$  Long term monitoring of the current @ 10 KV

Gap rejected if at the end: I @10KV >  $|_{max}$  or

I@10KV Increase > 50% or OVC, Spikes of current

✓ Final check QC data in the DB

Total time needed for one Super Module :

4 + 1 = 5 weeks (including 20% contingency)

#### Conclusions (1)

#### • Bakelite:

HPL batch # 10,11&13 +12 Measurements are done, data ready to be uploaded

• Electronics ON :

QC testing established, Under production, DB ready

#### • Gaps :

QA & QC established, list of components and equipment established, DB ready, software tools under development

• Chambers Assembly :

QA&QC established , list of components ready, procurement on going, DB ready,

• RPCs characterization :

Cosmic stands under construction, Architecture of the Trigger and DAQ defined, online under development, analysis software not yet started (in discussion), cosmic table & interface not ready

- Super Module : QA & QC to be finalized, DB to be developed
- P5 (Instal & com.) : Procedures & tests to be defined (QC-5)

### Conclusions (2)

- Every step of the construction from the bakelite production until the super module certification is maintained under a central control
- Activities in the different production sites are synchronized through the DataBase
- Procurement is centralized
- Documentation and traceability for each component
- All measurements recorded for each gap & chamber allowing a complete assembly and cosmic test history
- Construction DB in progress we aim to complet all QC by the end of the year