# Gas system upgrade for RE4


► RPC gas system status for RE4

Cost estimate and schedule for the production of the distribution racks

RE4 EDR 24 November 2011

Roberto Guida PH-DT-DI

## RPC gas system: missing parts for RE4




X 1 supply and 1 return pipe (per side) are already in the mini-cable chain and they arrive to the X3 balcony level on YE3

X 1 supply and 1 return pipe (per side) arrive only to the X2 balcony level on YE1 (i.e. the part from X2 to X3 and the cable chain is missing)

 $\mathbf{X}$  2 distribution racks need to be built.

X the gas distribution on the disks is missing



### RPC gas system status: few pictures

1 supply and 1 return pipe (per side) are already in the minicable chain and they arrive to the X3 balcony level on YE3






1 supply and 1 return pipe (per side) arrive only to the X2 balcony level on YE1 (i.e. the part from X2 to X3 and the cable chain is missing)

#### >1 supply and 1 return (per side) STOP BEFORE the mini-cable chain


#### RPC gas system status: few pictures



the pipes for the gas distribution on the disks are missing

Space available for the installation of the RE4 rack

RE3 rack




11/24/2011

### RE4 distribution racks

After several discussion about the number of gas channels, the conclusion was that 36 channels are fine (3 spare channels will be available on each rack)

≻Rack size will be 600 mm x 600 mm like normal gas distribution rack in the Endcap



QUICK

### RE4 distribution racks

#### Cost estimate: ≻49980 CHF/rack

#### ▶99960 for the 2 racks

#### Details:

rack	kCHF				
Material	35.38				
Manpower	14.5				

≻There are expensive components that account already for 75 % of the material cost:

Material	kCHF				
Quick connectors	21.6				
Soft pipes	5.5				

The cost for the 6 distribution manifolds is not charged because they were part of the original production

Name	Specifications		RPC		Price	Tot.price	Tot price
			1 rack	2 racks	1 pce	1 Rack	2 racks
Nb of rack	Rack 600x600x1800	SCEM: 06.61.74.003.0	1	2	1174	1174	2348
Bottom rack		SCEM: 06.61.74.410.9	1	2	59.5	59.5	119
Rack square		SCEM: 06.61.74.120.6	1	2	48	48	96
Nb of manifolds13 ways Input	Drawing nb 1		3	6	0	0	0
Nb manifolds 13 ways Output	Drawing nb 2		3	6	0	0	0
Tape for cell	Type M6 x 6 Legris	SCEM: 41.34.26.320.4	108	216	1.1	118.8	237.6
Tape for manifolds	Type M6 x 6 Legris	SCEM: 41.34.26.320.4	108	216	1.1	118.8	237.6
Tape for manifolds input	Type 3/8" LEGRIS	SCEM: 41.34.26.328.6	3	6	1.5	4.5	9
Tape for manifolds Output	Type 1/2" LEGRIS	SCEM: 41.34.26.330.2	3	6	2.05	6.15	12.3
Joints for cell	O'ring NBR ID 6.07X1.78mm	SCEM: 36.10.30.452.9	108	216	0.06	6.48	12.96
Joints for quick	Joints plat universel, 13x18x2 NBR	SCEM:36.12.60.405.9	108	216	0.16	17.28	34.56
Vis de fixation cell	Vis M3x16	SCEM: 47.62.71.107.5	432	864	0.08	34.56	69.12
Quick on manifolds input	SERTO Femelle 760I 1/4"Male	SCEM: 41.61.25.130.9	54	108	100	5400	10800
Quick on manifolds output	SERTO Male 760I 1/4"Male	SCEM: 41.61.25.110.3	54	108	100	5400	10800
Quick on soft tube input	SERTO Male 760I 1/4"Femelle	SCEM: 41.61.25.120.1	54	108	100	5400	10800
Quick on soft tube output	SERTO Femelle 760I 1/4"Femelle	SCEM: 41.61.25.140.7	54	108	110	5940	11880
Soft tube 1 length	Assiwell 400 mm		54	108	52	2808	5616
- Television (1997) - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997	Assiwell 400 mm + 100mm fixe tu	be	54	108	50	2700	5400
Joints quick/soft tube	Joints plat universel, 13x18x2 NBR	SCEM: 36.12.60.405.9	54	108	0.16	8.64	17.28
Bulkhead coupling input	FBO 4/6 to 4/6 LAITON	SCEM: 41.33.20.608.1	54	108	15.5	837	1674
Bulkhead coupling output	FBO 6/8 to 6/8 LAITON	SCEM: 41.33.20.608.1	54	108	17.5	945	1890
Adaptator connector union	FBO: diametre 16 laiton 3/8" cyl	SCEM: 41.33.10.216.8	4	8	14	56	112
Adaptator connector union	FBO: diametre 20 laiton 1/2" cyl	SCEM: 41.33.10.220.2	4	8	17	68	136
Manual valves 2 ways	Vanne a bille 3/4"		2	4	54	108	216
Manual valves 2 ways	Vanne a bille 1/2"		2	4	49	98	196
Raccords vannes	FBO : diametre 16 3/4"	SCEM: 41.33.10.616.6	4	8	14.5	58	116
Raccords vannes	FBO : diametre 22 1/2"	SCEM: 41.33.10.228.4	4	8	18	72	144
Bubbler	Protection		2	4	410	820	1640
Bubbler purge and backup			4	8	310	1240	2480
Bubbler purge			1	2	43.5	43.5	87
Pneumatique valve backup	Bachofen NO Type: 188.15.16.1.4.	1R.S0104	2	4	179	358	716
Regulation valve backup	tescom SO	CEM 59.75.10.100.6	2	4	384	768	1536
				0			
Pressure sensor input	sensors technic 0+40 mbar S	CEM 22.64.11.030.5	2	4	191	382	764
Pressure sensor output	sensors technic -10/+10 mbar	SCEM 22.64.11.005.6	2	4	191	382	764
Manpower	Mecanic part		1	2	12500	12500	25000
Manpower	Electrical part + material		1	2	2000	2000	4000
						49980.21	99960.42

11/24/201<u>The 2 racks will be ready for September 2012</u>

#### Conclusions

Some pipe work in the cavern is needed

>2 distribution racks need to be built

≻Total cost for the 2 gas distribution racks is 100 kCHF

The two racks will be ready for September 2012

≻The distribution racks will be installed as soon as possible during the long shutdown 2013 (The installation includes also some service cable to operate and control the racks status)

 $\triangleright$ Andrea d'Auria is the technician in our group responsible for the construction and installation of the racks.